BILL OF QUANTITIES

Item No.	Description	Ref: Std.Data Book PWD Item No.	Unit	Total Quantity	Rate	Amount in Figures (Rs.)	Amount in Words (Rs.)
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
1	Earth work excavation in ordinary soil and depositing on bank with initional lead of 50 m and lift upto 1.5 m including breaking clods, watering, ramming and sectioning of spoil bank etc. complete	51	10 m^3	683 m^3			
2	Cement concrete 1:4:8 (1 cement, 4 sand, 8 broken stone) uising 40 mm broken stone for including cost of materials, labours, curing etc.	111	m^3	61 m^3			
3	Reinforced cement concrete 1:2:4 (1 cement 2 sand 4 broken stone) using 20 mm broken stone including , watering, curing etc. complete but excluding reinforcement & formwork	122	10 dm^3	252 m^3			
4	R.C.C. 1:1.5:3 (1 cement, 1.5 sand, 3 broken stone) 20 mm broken stone includingall formwork, cost of materials, labour, curing etc. complete but excluding reinforcement	122(a)	10 dm^3	135 m^3			
5	Reinforcement (defomed bars confirming to IS 1786) for RCC work cutting, bending, lying and placed in position (Plain grill requiring bending cold).	130	Qtl.	3048 Kg			

6	Earth work excavation in or under water or in liquid mud in drain	-	10 m^3	694m^3			
7	Conveyance of the excavated earth and debries with in a distance of 5 km by lorry.	60 (C)	m3	875 m^3			
8	Engaging man coolies for placing the slabs in position.	-	E	70 Nos.			
9	Form work for R.C.C.works including wooden planks, joists, bamboo posts, and labour for taking down after completion of works.	132(b)	10 m^2	2349 m^2			
	TOTAL :						